

## Rooftop Solar Quotation

Date of Quotation: 2025-11-22 T05:43:25.365Z

To: Shri Mukunda Chougule

Phone: 9860981410

Address: Sangli 416416

Consumer No : 279940982353

Name on the Electricity Bill:

Sou Ujawala Mukunda Chougule

From:

**One Ohm Sustainable Green Energy Pvt  
Ltd**

OneOhm, Plot No. - 93, Vasantdada Industrial Estate, Near Old  
RTO Office, Sangli - 416416

Contact: +91 9225099702

Installer Contact: 979797 95 98



### Solar PV Generating System Solar Quotation

| Details                                               | UoM | Amount                |
|-------------------------------------------------------|-----|-----------------------|
| Type of Rooftop Solar System                          | -   | On Grid Rooftop Solar |
| System Size* (rounded- for example, 3.24 kWp ~ 3 kWp) | kWp | 3                     |
| Total Wattage Offered (DC Capacity)                   | Wp  | 3200                  |

| Details                           | UoM | Amount      |
|-----------------------------------|-----|-------------|
| Quoted Project Price (excl taxes) | ₹   | 172635.45   |
| GST: 5% on 70% project value      | ₹   | 6042.24     |
| GST: 18% on 30% project value     | ₹   | 9322.31     |
| Quoted Project Price (inc. taxes) | ₹   | 1,88,000 /- |
|                                   |     |             |
| Quoted Project Price (inc. taxes) | ₹   | 1,88,000 /- |

This quotation is generated using the software provided by OneOhm Green Energy Technologies Pvt.

Ltd. email: [info@OneOhm.co](mailto:info@OneOhm.co) Mobile: +918788275659

|                                   |   |             |
|-----------------------------------|---|-------------|
| Final Project Price (incl. taxes) | ₹ | 1,88,000 /- |
|-----------------------------------|---|-------------|

### Central Finance Assistance (CFA)/ Subsidy Impact (Illustration)

| Details                                            | UoM | Amount      |
|----------------------------------------------------|-----|-------------|
| Final Project Price (incl. taxes)                  | ₹   | 1,88,000 /- |
| *CFA/ Subsidy Amount (Direct Beneficiary Transfer) | ₹   | 78,000      |
| Effective Project Price (net of subsidy)           | ₹   | 1,10,000 /- |

\*Central Finance Assistance/ Subsidy is applicable for residential rooftop solar projects only. There are tax benefits for commercial and industrial rooftop solar installations through GST input and Accelerated Depreciation. Actual subsidy may vary slightly based on the actual wattage provided during project implementation. OneOhm Green Energy Technologies Pvt. Ltd. ("OneOhm") makes no representation, warranty, or guarantee regarding the availability or amount of such central finance assistance/ tax benefits. OneOhm merely facilitates the process that exists for obtaining these incentives. The customer has to pay the **Final Project Price (incl. taxes)** as per the payment milestones mentioned below. These milestones are not linked with the subsidy payment by the central government.

The subsidy will be applicable as per the date of the previous application if the customer has applied on the PM Surya Ghar Portal before starting their project with OneOhm Green Energy Technologies Pvt Ltd. OneOhm has no control over this process.

### Project Completion Timeline Quotation Validity

| Details                                                                                                                                             | UoM   |                           |
|-----------------------------------------------------------------------------------------------------------------------------------------------------|-------|---------------------------|
| Project Completion Period<br>(timeline from the advance payment date to the net meter installation - excluding the payment delays by the customer)) | Weeks | 16                        |
| Quotation Validity                                                                                                                                  | Date  | 2025-11-22 T05:43:25.365Z |

### Payment Milestones\*

| Details                                                                                                                                    | UoM | %   | Amount   |
|--------------------------------------------------------------------------------------------------------------------------------------------|-----|-----|----------|
| Advance Payment on Project Confirmation<br>(payment to be made <u>before</u> permissions work, design, detailed site survey)               | ₹   | 30% | 56,400   |
| Post Solar Sanction Milestone<br>(payment to be made <u>before/for</u> procurement, material delivery)                                     | ₹   | 65% | 1,22,200 |
| Final Amount on Commissioning<br>(system installation, discom inspection & payment to be made <u>after</u> meter installation from discom) | ₹   | 5%  | 9,400    |

This quotation is generated using the software provided by OneOhm Green Energy Technologies Pvt. Ltd. email: [info@OneOhm.co](mailto:info@OneOhm.co) Mobile: +918788275659

\*The customer agrees to pay the Final Project Price (incl. taxes) per the payment milestones mentioned in the payment schedule. These milestones are not linked with the subsidy disbursal by the central government. The payment milestones for customers who opt for loans are different.

### Project Bill of Materials

| System Component                  | Details                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
|-----------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Solar Panels</b>               | <p>Manufacturer - <b>Adani/Premier/Waaree Bifacial</b> , Category- <b>Half Cut Bi Facial</b>, Panel Rated Capacity - <b>540Wp-550Wp</b>, #<b>06</b> panels, Performance Warranty - <b>30 years</b>, Product Warranty - <b>12 years</b> provided by OEM</p> <p>Wp rated capacity of the panels may vary slightly based on the availability of the panels. The best-rated capacity available in the same category will be provided. (For Ex. Wp rated capacity of TopCON N-Type panels varies between 560 Wp to 580 Wp, whichever is available with the manufacturer will be provided at the time of installation)</p> |
| <b>Inverter</b>                   | <p>Inverter- <b>Solaredge   3-ph (with 6 Optimizers for 16panels)</b>, <b>3</b> kWp, #<b>1</b> inverters</p> <p>Inverter Warranty - <b>8 years</b> provided by OEM</p>                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| <b>Mounting Structure</b>         | <p><b>Elevated -Min 6ft x Max to 8ft - GI</b></p> <p><b>Structure:</b> <i>Galvanized MS pre-fabricated 3-purlin mounting structure with all nut-bolts in SS304 grade and A-Raymond clamps for fast installation, uniform pressure on module frame and reduced risk of glass damage, designed as per IS 875 wind load and site tilt/orientation</i></p> <p><b>Foundation:</b> <i>Non-penetrative precast RCC M25 grade blocks with protective padding to safeguard roof waterproofing and safely transfer loads without core-cutting/grouting</i></p>                                                                 |
| <b>DC Cables</b>                  | Polycab/ KEI/ RR brand - 4 Sqmm Solar-grade, UV protected, 1100V with PVC conduits                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| <b>Load Side (AC) Cables</b>      | Polycab/ KEI/ RR brand- 2C/4C x 2.5 / 4 /6 / 25/ 35 / 50/ 75/ 95 sq mm, Al / Cu. The c/s area of the load side cable will vary based on the system's kWp size.                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| <b>Module Connector</b>           | Elcom/ Nigbo Brand - 4 sq. mm Solar-grade IP65                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| <b>Earthing</b>                   | <p>Maintenance Free - COPPER BONDED EARTH ELECTRODE - Chemical Earthing as per IEC/IS 62305 [1.2 meters Rod Copper bonded] with Earth pit Chambers</p> <p>Earthing and Earthing Cable: 16 sq mm Aluminium down conductor of reputed brand</p>                                                                                                                                                                                                                                                                                                                                                                        |
| <b>Lightening Arrestor</b>        | OneOhm Approved Reputed- provides Protection as per BS EN/IEC 62305 with NFC and CPRI tested                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |
| <b>ACDB</b>                       | OneOhm Approved Reputed - with CB + SPD                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |
| <b>Accessories</b>                | Reputed OneOhm Approved- Hardware and Accessories                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| <b>Net &amp; Generation Meter</b> | <p>Generation Meter - MSEDCL Approved - HPL/ L&amp;T - 1/3 Phase</p> <p>Net Meter - Installed by MSEDCL's approved vendors</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
| <b>Remote Monitoring System</b>   | Included in smart inverter - With wifi/ GSM System                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |
| <b>Safety Requirements</b>        | Standard - as per site Requirement                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |

This quotation is generated using the software provided by OneOhm Green Energy Technologies Pvt.

Ltd. email: [info@OneOhm.co](mailto:info@OneOhm.co) Mobile: +918788275659

yw8UqqExT0-HzFQKO8ZwEA

EzyknePdSCeteApFau5lww

## Solar Installer Bank Account Details

|                   |                                                 |
|-------------------|-------------------------------------------------|
| <b>Name</b>       | Oneohm Sustainable Green Energy Private Limited |
| <b>Bank Name</b>  | State Bank of India                             |
| <b>A/c Number</b> | 43432696314                                     |
| <b>IFSC Code</b>  | SBIN0001501                                     |

## Additional Comments (if any)

The Load Extension Charges are not included in this quotation. The customer is to pay the load extension charges as per the MSSEDCL quotation.

## Maintenance:

- OneOhm shall provide **five-year** free workmanship maintenance (consumables not included) for residential projects. And **one-year** free workmanship maintenance (consumables not included) for commercial and industrial projects. Only those customers who have paid all their dues will be eligible for the 'free workmanship maintenance'.
- OneOhm shall visit the client's premises once every quarter after the commissioning of the RTS System for maintenance purposes.
- During such maintenance visits, OneOhm's maintenance team shall check all nuts and bolts, fuses, earth resistance, and other consumables regarding the RTS System to ensure that it is in good working condition.
- Cleaning is the client's responsibility, the minimum expectation from the client is that the solar plant will be cleaned regularly as per the dusting frequency.

## Solar Installer Scope of Work

- Detailed Site Survey & Design of the solar photovoltaic plant
- Shadow Analysis (wherever necessary)
- Supply of all equipment as per the Bill Of Materials (BOM)
- Installation & mounting of solar PV panels on rooftops as agreed and as specified in the site survey section of this proposal.
- Installation & commissioning of inverters, AJB, ACDB, Earthing system & all other items associated with subject solar system BOM
- Associated cabling and electrical works of solar plant
- Commissioning and successful trial run of solar plant
- Solar net metering related MSSEDCL (DISCOM) approvals and sanctions as well as liaising
- The solar installer may suggest alternate materials if (in unforeseen circumstances) the quoted material is not available at the time of installation.

## Client Scope

Shadow-free & south-facing area for panel installations

- Additional charges to be borne by the client for additional material required other than covered in BOM
- Internet connectivity for remote monitoring system
- Provide suitable indoor space for inverter mounting
- Provide suitable space for Earthing
- Contract/ Sanctioned Load Extension Deposit/ Name change fees (wherever applicable as per the MSEDCL charges)
- DISCOM may require the customer to visit the DISCOM office to sign the net metering agreement. The customer may have to comply with that.
- Regular milestone-based payments are in the client's scope. The solar installer is merely a service provider, not an investor in the solar plant at the customer's property. The solar installer will not be responsible for any delays caused because of the delays in payments from the client. The materials (including solar panels and inverters) will be procured only after the client's 'post solar sanction payment' (2nd milestone) is completed. Suppose the customer fails to pay any sum due under this purchase order on the due date. In that case, the solar installer may suspend its obligations under this purchase order until all outstanding amounts (including interest @1.25% per month are due) are paid.
- Provide requisite power, water, and other requisite resources (if any) and storage facilities for construction, installation, operation, and maintenance of the RTS System at zero cost to the solar installer;
- Permit geo-tagging of the customer's site as the solar installer's installation site;
- Unless otherwise intimated by the customer in writing, the solar installer is entitled to take photographs, videos and testimonials of the customer and the customer's site, and to create content that will become the property of the solar installer and the same can be freely used by the solar installer as part of its promotional and marketing activities across all platforms as the solar installer deems fit;
- The customer to validate the stability of the customer's site for installation of the RTS System.
- The client is responsible for providing the appropriate documentation for the loan process. The OneOhm teams can only facilitate the process.
- To avail Solar rooftop loan, all banks have different guidelines in relation to the stamp paper requirement. The stamp/bond charges are payable by the customer to avail solar loan facility.

## Timelines

- Please note that the project timelines are dependent on the DISCOM timelines. DISCOM has its SOPs and they tend to follow their process.
- Change of name on the electricity bill (if needed) generally may take about 4-6 weeks. One billing cycle is required to reflect the new name on the electricity bill.
- Load Extension (if needed) generally may take about 4-6 weeks. One billing cycle is required to reflect the new load on the electricity bill.

---

This quotation is generated using the software provided by OneOhm Green Energy Technologies Pvt. Ltd. email: [info@OneOhm.co](mailto:info@OneOhm.co) Mobile: +918788275659

- Solar Application to Solar Sanction from MSEDCL generally takes about 2 weeks (15 working days according to the MSEDCL SOP)
- Post Solar Sanction, the system installation can only be done after the customer's Post Solar Sanction Milestone.
- After the Post Solar Sanction Milestone, the material (post-solar sanction payment) may be delivered within 10-12 days approximately subject to the market availability of the materials.
- After installation, a work completion report is submitted to MSEDCL. The solar plant at your property is commissioned after meter installation by MSEDCL. This process may take about 3 weeks. (The timeline as per MSEDCL SOP is 20 working days)
- any timeline or schedule shared by the solar installer for the provision of services and delivery of the RTS system is only an estimate and the solar installer will not be liable for any delay that is not attributable to the solar installer.

### Order Cancellation

- The customer may cancel the order placed on the solar installer within 7 (seven) days from the date of remittance of advance money or the date of order acceptance, whichever is earlier ("Order Confirmation") by serving a notice.
- If the customer cancels the order after the expiry of 7 (seven) days from the date of the advance money payment or the date of order acceptance, whichever is earlier, the customer shall be liable to pay the solar installer, a cancellation fee of 5% of the total order value plus costs and expenses incurred by Vendor, including, costs for labor, design, return of products, administrative costs, and subvention costs.
- Notwithstanding the aforesaid, the customer shall not be entitled to cancel the order after the vendor has dispatched the RTS System (or any part thereof, including the module Mounting Structure or any Balance Of System materials) to the customer's Site. If the customer chooses to terminate the order after dispatch, the entire amount paid by the customer to date shall be forfeited by the solar installer.

### Force Majeure

- The following clauses that substantially affect the performance of the Contract shall only be considered Force Majeure conditions.
- Any delays because of the change in policies and/or processes from the policy makers including but not limited to MNRE, REC, MSEDCL, MEDA (any other DISCOM)
- Natural phenomena including but not limited to floods, droughts, earthquakes, heavy rains, cyclones, and epidemics.
- Acts of any Government, domestic or foreign including but not limited to war, declared or undeclared quarantines, and embargo.
- Any changes in country laws, trade restrictions, imposition of penal duties, and levies adversely affecting the continuation of contractual commitments.

Thank you for your consideration, we look forward to hearing from you.

Go to **OneOhm App** to complete your purchase!

---

This quotation is generated using the software provided by OneOhm Green Energy Technologies Pvt.  
Ltd. email: [info@OneOhm.co](mailto:info@OneOhm.co) Mobile: +918788275659